



## River Drive Wastewater Treatment Plant

Circleville, Ohio, USA



Completion Date  
**2019**

Owner  
**EARNHART HILL REGIONAL  
WATER & SEWER DISTRICT**

Engineer  
**CT CONSULTANTS, INC.**

Ready Mix Supplier  
**ROSS-CO READY MIX**

Contractor  
**MECHANICAL  
CONSTRUCTION CO.**

Products  
**BIO-SAN C500**

Project Type  
**WASTEWATER  
TREATMENT PLANT**



This project involves construction of additional structures at the existing River Drive WWTP including 2 digesters, a sludge tank and a sludge drying bed. A total of 1,100 yd<sup>3</sup> (840 m<sup>3</sup>) were treated with **Bio-San C500**, dosed at 1% (5.6 lb. per yd<sup>3</sup>/2 kg per m<sup>3</sup>) based on a cementitious content of 564 lbs. per yd<sup>3</sup> (256 kg/m<sup>3</sup>).

